



## **Aga Khan Rural Support Programme (AKRSP) – Request for Quotation (RFQ)**

AKRSP invites sealed quotations from experienced contractors, fabricators, suppliers, and construction firms for the **Supply, Transportation, Installation, and Completion of Fencing Works at nine (09) Demonstration Sites (approximately 2 Kanal each)** located in Upper and Lower Chitral.

### **Project Locations**

- Kosht Ghoru, Laspur Raman, Booni Dokandeh, Reshun Raghain, Parwak Bala (Upper Chitral)
- Garam Chashma Center, Drosh, Kari Bala, Arkari Oveer Lasht (Lower Chitral)

### **Scope of Work**

The assignment includes:

- Excavation and concrete works for fence posts
- Supply and installation of angle iron supports
- Supply and fixing of galvanized barbed wire
- Transportation of materials to project sites
- Complete fencing installation and finishing works

**RFQ Issue Date:** June 05, 2026

**Quotation Submission Deadline:** June 15, 2026

AKRSP reserves the right to accept or reject any or all quotations without assigning any reason. Child labor is strictly prohibited.

For detailed RFQ documents and further information please visit the link provided below.

### **Admin & Procurement Officer**

Aga Khan Rural Support Programme (AKRSP)  
Regional Programme Office, Chitral



Aga Khan Rural Support Program (AKRSP)  
REQUEST FOR QUOTATION (RFQ)

RFQ No: AKRSP/ 0215/2026    Delivery Point:    **Different locations**

RFQ Date: **June 05, 2026**,    Submission Date:    **June 15, 2026**

**Subject: Request For Quotation (RFQ)- For Fencing Works Of 2 Kanal Demonstration Site**

**1. INTRODUCTION**

The Aga Khan Rural Support Programme (AKRSP) invites sealed quotations from experienced contractors, fabricators, suppliers, and construction firms for the supply, transportation, installation, and completion of fencing works for Nine (09) sites, each having an approximate area of two (02) Kanal. The assignment includes excavation, concrete works, supply and installation of angle iron supports, supply and fixing of galvanized barbed wire, transportation of materials to the project site, and all allied works necessary for complete execution.

The objective of the assignment is to establish a durable and secure perimeter fencing system that protects the project area from unauthorized access, livestock intrusion, and other external disturbances. The successful bidder shall be responsible for carrying out all activities in accordance with approved specifications, good engineering practices, and AKRSP requirements.

Interested firms and contractors having relevant experience in fencing, steel fabrication, and civil works are encouraged to participate in this competitive procurement process. The demonstration sites are located at:

<b>S. No.</b>	<b>Location</b>	<b>District</b>
<b>1</b>	Kosht Ghoru	Upper Chitral
<b>2</b>	Laspur Raman	Upper Chitral
<b>3</b>	Booni Dokandeh	Upper Chitral
<b>4</b>	Reshun Raghain	Upper Chitral
<b>5</b>	Parwak Bala	Upper Chitral
<b>6</b>	Garam Chashma Center	Lower Chitral
<b>7</b>	Drosh	Lower Chitral
<b>8</b>	Kari Bala	Lower Chitral
<b>9</b>	Arkari Oveer Lasht	Lower Chitral

The assignment includes excavation, concrete works, supply and installation of angle iron supports, supply and fixing of galvanized barbed wire, transportation of materials to the respective project sites, and all allied works necessary for complete execution.

The objective of the assignment is to establish durable and secure perimeter fencing systems around the demonstration sites to protect them from unauthorized access, livestock intrusion, and other external disturbances. The successful bidder shall be responsible for carrying out all activities in accordance with approved specifications, good engineering practices, and AKRSP requirements.

Interested firms and contractors having relevant experience in fencing, steel fabrication, and civil works are encouraged to participate in this competitive procurement process.

## 2. SCOPE OF WORK

The contractor shall provide all labor, tools, equipment, transportation, supervision, consumables, and materials required for the complete execution of the fencing works at the above-mentioned demonstration sites.

The scope shall include, but not be limited to, the following:

- Site inspection and verification of dimensions at each location.
- Excavation for fence post foundations.
- Supply and placement of plain cement concrete.
- Supply of angle iron supports as specified.
- Transportation of all materials to the respective project sites in Upper and Lower Chitral.
- Supply and installation of galvanized barbed wire.
- Alignment, tensioning, fixing, and finishing of fencing.
- Site cleaning and disposal of construction waste.
- Rectification of any defects observed during inspection.

The contractor shall be deemed to have visited the sites and familiarized himself with the local conditions, accessibility, transportation requirements, and other relevant factors before submitting the quotation.

## 3. BILL OF QUANTITIES (BOQ)

S. No	Description of Work	Quantity	Unit	Rate	Amount
1	Excavation in foundation in shingle/gravel for Angle Iron Support of size (1' × 1' × 2'), Total Posts = 53	106.0	Cft		
2	Plain Cement Concrete including placing, compacting, finishing and curing (Ratio 1:3:6) for Angle Iron Supports of size (1' × 1' × 2'), Total Posts = 53	106.0	Cft		
3	Supply of Equal Angle Iron Supports, 53 Nos., Length 6'-8", Size 1.5" × 1.5", Thickness 5 mm	301.0	Kg		
4	Supply of High Tensile Galvanized Barbed Wire, 4-point barbs at 5-inch spacing, 12 SWG (2.64 mm dia), approximately 5 rolls of 25 kg each	125.0	Kg		
5	Transportation of Angle Iron Supports and Barbed Wire to Project Site	426.0	Kg		
6	Installation of Angle Iron Supports at 8 ft C/C spacing and Barbed Wire at 8-inch spacing in six rows complete in all respects	53	Posts		

**Total Quoted Cost (PKR):** \_\_\_\_\_

## **4. TECHNICAL SPECIFICATIONS**

### **4.1 Excavation Works**

Excavation shall be carried out carefully to the specified dimensions of one foot by one foot by two feet depth for each support post location. The excavated pits shall be properly aligned to ensure a straight fencing line and shall be free from loose material before concrete placement. Any over-excavation shall be made good by the contractor at his own cost.

### **4.2 Concrete Works**

Plain Cement Concrete shall be prepared using a mix ratio of 1:3:6. Cement shall be fresh and free from lumps. Sand shall be clean and well graded, while coarse aggregate shall be hard and durable. Concrete shall be thoroughly mixed, properly compacted, and cured for a minimum period necessary to achieve the required strength.

### **4.3 Angle Iron Supports**

The angle iron supports shall be equal angle sections measuring 1.5 inches × 1.5 inches with a minimum thickness of 5 mm. Each support shall have a total length of 6 feet 8 inches. All steel shall be free from rust, bends, cracks, or manufacturing defects. AKRSP reserves the right to reject any substandard material.

### **4.4 Barbed Wire**

Barbed wire shall be high tensile galvanized steel, 12 SWG (2.64 mm diameter) with four-point barbs at 5-inch spacing. Galvanization quality shall be suitable for outdoor exposure and resistant to corrosion. Damaged, rusted, or low-quality wire shall not be accepted.

### **4.5 Installation**

Posts shall be installed at 8-foot center-to-center spacing. Barbed wire shall be fixed in six horizontal rows at approximately 8-inch spacing. Proper tensioning shall be maintained throughout the fence line to avoid sagging. The finished fence shall be straight, stable, and capable of withstanding environmental loads and routine use.

## **5. EVALUATION CRITERIA**

AKRSP shall evaluate quotations based on technical compliance, bidder capability, quality of proposed materials, past performance, and quoted price.

The lowest-priced quotation shall not necessarily be accepted. AKRSP reserves the right to select a bidder offering the best value considering quality, durability, reliability, delivery capability, and overall compliance with project requirements.

AKRSP may conduct verification of information submitted by bidders before award of contract.

## **6. TERMS AND CONDITIONS**

### **6.1 Site Verification**

The bidder shall be solely responsible for visiting the project site before submitting the quotation and verifying all dimensions, accessibility conditions, terrain characteristics, transportation arrangements, and any challenges affecting execution of works. Submission of a quotation shall be considered confirmation that the bidder has fully understood the site conditions and associated risks. No additional payment shall be entertained later on the grounds of lack of site knowledge or misunderstanding of local conditions.

## **6.2 Inclusive Pricing**

The quoted rates shall be comprehensive and shall include all costs related to labor, supervision, transportation, loading, unloading, equipment, tools, fuel, taxes, duties, profits, overheads, safety measures, and incidental expenses. The contractor shall not claim any additional compensation beyond the approved purchase order amount except where formally approved by AKRSP through written variation orders. Any omitted cost necessary for completion of the works shall be deemed included in the quoted rates.

## **6.3 Material Quality Assurance**

All materials supplied under this contract shall strictly conform to the specifications provided in the RFQ. AKRSP reserves the right to inspect materials before transportation, during installation, and after completion of works. Any material found defective, damaged, rusted, below specification, or unsuitable for intended use shall be immediately replaced by the contractor at no additional cost. Acceptance of materials at site shall not relieve the contractor from responsibility for quality.

## **6.4 Inspection and Testing**

AKRSP representatives shall have unrestricted access to inspect the works at any stage of execution. The contractor shall facilitate measurements, verification of quantities, examination of material quality, and inspection of workmanship whenever requested. If any work is found non-compliant with specifications, the contractor shall rectify deficiencies promptly at his own expense and within the timeframe specified by AKRSP.

## **6.5 Workmanship Standards**

All works shall be executed in a professional manner by skilled personnel having relevant experience in fencing installation. Alignment, spacing, concrete placement, wire tensioning, and finishing shall be carried out according to recognized engineering practices. AKRSP may require correction or replacement of any poorly executed work that compromises safety, durability, or appearance of the fencing system.

## **6.6 Completion Timeline**

The successful contractor shall mobilize resources immediately upon issuance of the Purchase Order or Work Order. The entire assignment shall be completed within the timeframe agreed between AKRSP and the contractor. Delays attributable to poor planning, insufficient manpower, equipment shortages, or contractor negligence shall not be considered valid reasons for extension of time.

## **6.7 Liquidated Damages for Delay**

In the event of unjustified delays in completion of the works, AKRSP reserves the right to impose liquidated damages. Such deductions may be calculated as a percentage of the contract value for each day of delay, subject to limits determined by AKRSP. Continued failure to complete the works may result in contract termination and recovery of losses from the contractor.

## **6.8 Health and Safety Compliance**

The contractor shall be responsible for ensuring a safe working environment throughout the project period. All workers shall be provided with appropriate personal protective equipment and trained in safe working practices. The contractor shall remain fully liable for accidents, injuries, damages, or claims arising from execution of the works and shall indemnify AKRSP against related liabilities.

## **6.9 Environmental Protection**

The contractor shall take reasonable precautions to minimize environmental impacts during execution of the works. Excavated material, waste, packaging, scrap metal, and other debris shall be managed

responsibly and removed from the site upon completion. Activities causing unnecessary damage to surrounding land, vegetation, or community assets shall be avoided and rectified where required.

#### **6.10 Transportation Responsibility**

The contractor shall be fully responsible for loading, transportation, unloading, and safe delivery of all materials to the designated project location. Any loss, theft, damage, or deterioration occurring during transportation shall remain the responsibility of the contractor. AKRSP shall not compensate for materials damaged before formal acceptance at site.

#### **6.11 Defect Liability Period**

The contractor shall remain responsible for defects in workmanship and materials for a period of six months after completion and acceptance of the works. Any defects observed during this period, including loose posts, broken wire, poor tensioning, concrete failure, or material deterioration, shall be rectified promptly by the contractor without additional cost to AKRSP.

#### **6.12 Payment Terms**

Payment shall be made only after satisfactory completion of the works, submission of invoice, verification of quantities, and certification by AKRSP's authorized representative. AKRSP reserves the right to withhold payment for incomplete, defective, or non-compliant work until deficiencies have been rectified. Applicable taxes shall be deducted as per government regulations.

#### **6.13 Variations**

AKRSP reserves the right to increase or decrease quantities based on actual site requirements. Such adjustments shall be paid at the quoted unit rates unless otherwise agreed in writing. The contractor shall not commence additional work without written authorization from AKRSP.

#### **6.14 Right of Rejection**

AKRSP reserves the right to reject any or all quotations without assigning any reason and without incurring any liability toward participating bidders. AKRSP may cancel the procurement process, revise requirements, or re-advertise the assignment whenever considered necessary in the interest of the project.

#### **6.15 Contract Termination**

AKRSP may terminate the contract if the contractor fails to mobilize resources, delivers substandard materials, violates contractual obligations, engages in fraudulent practices, or repeatedly fails to meet project requirements. Upon termination, AKRSP may engage another contractor and recover additional costs incurred from the defaulting contractor.

#### **6.16 Compliance with Laws**

The contractor shall comply with all applicable laws, regulations, labor requirements, taxation rules, and local authority requirements relevant to the execution of the works. Any penalties arising from non-compliance shall be borne solely by the contractor and shall not constitute grounds for additional payment.

#### **6.17 Confidentiality**

All project-related information, documents, drawings, specifications, and correspondence provided by AKRSP shall be treated as confidential. The contractor shall not disclose such information to any third party without prior written authorization from AKRSP. This obligation shall remain valid even after completion of the contract.

### **6.18 Ethical Conduct**

The contractor shall maintain the highest standards of integrity and professional conduct throughout the procurement and implementation process. Any attempt to influence evaluation outcomes, provide inducements, misrepresent information, or engage in corrupt practices shall result in immediate disqualification and possible exclusion from future AKRSP procurements.

### **7. QUOTATION VALIDITY**

The quotation shall remain valid for a minimum period of ninety (90) calendar days from the submission deadline. During this period, the bidder shall not withdraw or modify the quotation without written consent from AKRSP.

### **8. AWARD OF CONTRACT**

The successful bidder shall receive a Purchase Order or Contract Agreement from AKRSP. The award shall become effective only upon written acceptance by both parties. The contractor shall commence work only after receiving official authorization from AKRSP.

**Sealed quotation should be submitted by hand or through courier at Regional Office AKRSP near Shahi Qilla Chitral by, 4:00 pm June 15, 2026.**

Admin & Procurement Officer

AKRSP Chitral

Declaration by Vendor

I/We, the undersigned, hereby certify that the information provided in this quotation is accurate and complete. We agree to abide by the terms and conditions laid out in this RFQ and confirm that we are eligible and capable of delivering the required services on time.

Vendor Name: \_\_\_\_\_ Address: \_\_\_\_\_

Contact Person: \_\_\_\_\_ Phone/Email: \_\_\_\_\_

KPRA Reg. No: \_\_\_\_\_ GST/NTN No: \_\_\_\_\_

Signature & Stamp: \_\_\_\_\_ Date: \_\_\_\_\_

# Drawings

